



CHARA Michigan Phase-tracker



*Fringe Tracking
in the
Near Infrared*

Dave Berger, John Monnier (Michigan)
Theo ten Brummelaar (CHARA/GSU)
Rafael Millan-Gabet (MSC)

CHARA Collaboration Meeting
20-24 Feb 2006, Tucson AZ






Overview


- ★ removes atmospheric and mechanically induced phase changes (“freezes the fringes”)
- ★ longer coherence and integration times
- ★ increased sensitivity
 - ★ for MIRC, ~3-4 magnitudes
 - ★ shorter path length modulation for PP combiners
- ★ separate fringe tracker from science combiner



Beam Combination Lab




adapted from J. Sturmann (priv. comm.)






Feeding CHAMP

- ★ gray (50/50) or chromatic (JHK) split options
- ★ “hot-swappable” mount design to minimize re-alignment
- ★ CaF₂ glass is being ordered
- ★ angles beam down to 4.5" height






Path Modulation




- ★ changes beam spacing to 2"
- ★ every other beam @ same freq
- ★ $\Delta \text{OPD} = 1\text{-}2 \lambda$'s at up to 500 Hz
- ★ resonent frequency @ 1.2 kHz
- ★ elliptical flat mirror on invar mount
- ★ design finalized, piezos ordered





Beam Combination


- ★ small AOI (~ 11 deg) --> 1" optics
- ★ pair-wise: 1+2, 2+3, 3+4, 4+5, 5+6, 6+1
- ★ moveable mirror for use with 2 to 6 telescopes
- ★ Infrasil glass is being ordered





Fiber Injection and Transport


- ★ multi- or many-mode fibers
- ★ easier beam transport
- ★ 2-D fiber array






Camera Dewar, Optics, and Detector

- ★ reimaging optics
- ★ 2 filter wheels
- ★ 1k x 1k Hawaii detector (same as at Keck)
- ★ 12 beams split between 4 amps
- ★ dewar design is finalized, detector at UM





Information Flow





Project Status

beam feeds

- CaF₂ glass being ordered

path modulation

- piezos have been lab tested and ordered
- design for custom mirror mount finalized
- elliptical mirrors at UM
- amplifiers have been ordered
- analog signal generator card and breakout box at UM

beam combiner

- Infrasil glass being ordered
- off the shelf mounts specified

camera

- dewar design finalized (delivery ~3 months)
- Hawaii chip and digital readout electronics at UM

computer

- computer at UM with Gentoo installed
- specified Xenomai RTOS

delay line control

- consultation with Hines & Irwin



Current Schedule

Spring '06

finish optical and mechanical fabrication

Summer '06

camera testing and dewar optics design

Fall/Winter '06

integrate camera with combiner and close loop with artificial turbulence; upgrades to CHARA VME

Summer '07

delivery to CHARA; sky testing